

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21055-00-00
Spot: NESWNE Sec/Twnshp/Rge: 13-31S-5E
3808 feet from S Section Line, 1850 feet from E Section Line
Lease Name: WAKEFIELD Well #: 3
County: COWLEY Total Vertical Depth: 2625 feet

Operator License No.: 5495
Op Name: MCPHERSON, BILL DBA MCPHERSON
Address: 15256 112TH RD
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2624		100 SX
SURF	8.625	160		75 SX

\$ 85.31

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2006 10:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL DBA MCPHERSON DRILLING CO.
Proposal Rcvd. from: BRENT WHITEMAN Company: GEN-DOR OIL CO. Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/28/2006 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7/17/2006 -- Sanded back at 2445'. Dump bailed 6 sacks of cement on top of sand.
7/25/2006 -- Shot 5-1/2" casing at 1476'. POOH with 34 joints of 5-1/2" casing.
7/28/2006 -- RIH with tubing at 250'. Gen-Dor mixed and pumped 100 sacks of 60/40 posmix with 4% gel to surface.
United Cement #7279

Perfs:

Top	Bot	Thru	Comments
2551	2557		
2538	2544		

RECEIVED
KCC DISTRICT #2
AUG - 2 2006
WICHITA, KS

INVOICED
DATE 8/31/06
2007 060469

RECEIVED

AUG 30 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)