

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21990-00-00
Spot: SESWNE Sec/Twnshp/Rge: 13-31S-5E
3018 feet from S Section Line, 1737 feet from E Section Line
Lease Name: WAKEFIELD Well #: 7
County: COWLEY Total Vertical Depth: 2650 feet

Operator License No.: 5495
Op Name: MCPHERSON, BILL DBA MCPHERSON
Address: 15256 112TH RD
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2649		100 SX
SURF	8.625	168		75 SX

\$ 86.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2006 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL DBA MCPHERSON DRILLING CO.
Proposal Revd. from: BRENT WHITEMAN Company: GEN-DOR OIL CO. Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/28/2006 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7/25/2006 -- Sanded back at 2450'. Dump bailed 6 sacks of cement on top of sand.
7/26/2006 -- Shot 4-1/2" casing at 1700', 1429', and 1176'. POOH with 30 joints of 4-1/2" casing (1176').
7/28/2006 -- RIH with tubing at 250'. Gen-Dor mixed and pumped 93 sacks of 60/40 posmix with 4% gel to surface.
United Cement #7279

Perfs:

Top	Bot	Thru	Comments
2574	2576		
2563	2570		

**RECEIVED
KCC DISTRICT #2
AUG - 2 2006
WICHITA, KS**

**RECEIVED
AUG 30 2006
KCC WICHITA**

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

a

PJT