

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20558-00-00  
Spot: SW Sec/Twnshp/Rge: 27-28S-8W  
1320 feet from S Section Line, 1420 feet from W Section Line  
Lease Name: NEVILLE Well #: 1  
County: KINGMAN Total Vertical Depth: 4141 feet

Operator License No.: 5254  
Op Name: MIDCO EXPLORATION, INC.  
Address: 414 PLAZA DRIVE #204  
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4133		125 SX CMT
SURF	8.625	213		200 SX CMT

\$ 134.58

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/24/2006 9:00 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCO EXPLORATION, INC. Phone: (630) 655-2260

Proposed Plugging Method: Set CIBP 50' above perforations; 35 sxs at 1200'; 35 sxs 700'; circulate 263' - 0'. Perforations 4133' - 4141'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/23/2006 11:00 AM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

A CIBP was set at 4100' and capped with 2 sacks of cement. Casing was recovered from 1303' and pulled from well bore. Tubing was ran to 1209' and 35 sacks of cement was spotted. Tubing pulled to 687' and 35 sacks of cement spotted. Tubing pulled to 259' and cement circulated to surface.

60/40 posmix with 4% gel

Allied Cement

**Perfs:**

Top	Bot	Thru	Comments
4133	4141		

RECEIVED  
KCC DISTRICT #2  
JUL 31 2006  
WICHITA, KS

RECEIVED  
AUG 30 2006

INVOICED

DATE 8/31/06  
TEL. NO. 200 7060470

Remarks:

Plugged through: TBG

District: 02

Signed [Signature]  
(TECHNICIAN)

KCC WICHITA

[Signature]

[Signature]