

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20015-00-00
Spot: SENESW Sec/Twnshp/Rge: 10-31S-3E
1649 feet from S Section Line, 2994 feet from E Section Line
Lease Name: HANN Well #: 1
County: COWLEY Total Vertical Depth: 3120 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3120		75 SX CMT
SURF	8.625	214		150 SX CMT

\$ 101,400

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2006 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: RON WHITEMAN Company: WHITEMAN, RON DBA GEN-DOR Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/14/2006 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

6/5/2006 -- Sanded back 70' above perforations at 3000'. Dump bailed 6 sacks of cement on top. Shot 5-1/2" casing at 1326'. POOH with 33 jts of 5-1/2" casing.

6/13/2006 -- RIH with tubing at 360'. Gen-Dor mixed and pumped 166 sacks of 60/40 posmix with 4% gel.

6/14/2006 -- Tagged cement at 167'. RIH with tubing at 165'. Gen-Dor mixed and pumped 60 sacks of 60/40 posmix with 4% gel to surface.

United Cementing #6699

Perfs:

Top	Bot	Thru	Comments
3071	3077		

RECEIVED
KCC DISTRICT #2
JUL 3 1 2006
WICHITA, KS

INVOICED
DATE 8/31/06
2007060479

RECEIVED
AUG 30 2006

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

KCC WICHITA

M

PPT