

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01927-00-00  
Spot: SESEW Sec/Twnshp/Rge: 25-18S-8W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: LANSING JR - A Well #: 4  
County: RICE Total Vertical Depth: 3142 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 225 MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3125		
SURF	10.38	211		

\$ 10212

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/07/2006 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/07/2006 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2950' and capped with 7 sacks of cement. Perforated at 1050', 700', and 270'. Ran tubing to 1050' and pumped 50 sacks of cement. Pulled tubing to 700' and pumped 50 sacks of cement. Pulled tubing to 270' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland #C030543

Perfs:

RECEIVED  
KCC DISTRICT #2  
JUL 14 2006  
WICHITA, KS

15-159-01927-00-00  
8/31/06  
200.706.0477

RECEIVED  
AUG 30 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

*M*

*PT*