

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02118-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 14-19S-9W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MAES Well #: 1
County: RICE Total Vertical Depth: 3259 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 225 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3225		125 SX CMT \$105.92
SURF	8.625	206		125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2006 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 06/27/2006 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2900' and capped with 5 sacks of cement. Log Tech perforated at 1150', 800', and 260'. Ran tubing to 1150' and pumped 35 sacks of cement. Pulled tubing to 800' and pumped 35 sacks of cement. Pulled tubing to 260' and pumped 50 sacks of cement. Pulled tubing and no circulation. Ran tubing back in in the hole to 260' and pumped 300 lbs of cotton hulls, 5 sacks of gel, and 100 sacks of cement. Cement circulated out of long string and surface casings

60/40 posmix with 4% gel

Copeland #C030597.

Perfs:

Top	Bot	Thru	Comments
3254	3257		
3245	3247		
3105	3109		
3091			
3085			
2989	2999		

RECEIVED
KCC DISTRICT #2
JUL 14 2006
WICHITA, KS

RECEIVED
AUG 30 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)