

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02190-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 20-19S-9W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: PROFFITT Well #: 1
County: RICE Total Vertical Depth: 3252 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 225 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3200		
PROD	5.5	3242		100 SX CMT
SURF	8.625	230		100 SX CMT

\$ 105.69

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2006 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: NONE
Date/Time Plugging Completed: 06/29/2006 10:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Ran sandline down, but couldn't get past 300'. Ran 2-3/8" tubing and work it down to 740'. Rigged up Copeland and pumped 5 sacks of gel and 250 sacks of cement. Circulated cement up long string and surface casing. Topped off with 25 sacks of cement.

60/40 posmix with 4% gel

Copeland #C030526

Perfs:

Top	Bot	Thru	Comments
3120	3125		
3084	3090		
2985	2989		

RECEIVED
KCC DISTRICT #2
JUL 14 2006
WICHITA, KS

INVOICED
DATE 8/31/06
200 7060477

RECEIVED
AUG 30 2006

Remarks:

Plugged through: TBG

KCC WICHITA

District: 02

Signed Virgil Clothier
(TECHNICIAN)

M

PST