

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02196-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 20-19S-9W
2070 feet from S Section Line, 5006 feet from E Section Line
Lease Name: ROLFS Well #: 4
County: RICE Total Vertical Depth: 3234 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 225 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3233		150 SX
SURF	8.625	246		

\$ 105.11

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2006 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/23/2006 12:00 AM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded bottom to 2900' with 5 sacks of cement. Perforated well at 1200', 800', and 300'. Ran in 2-3/8" tubing to 1200' and mixed 35 sacks of cement. Pulled to 800' and mixed 35 sacks of cement. Pilled to 300' and circulated cement to surface with 50 sacks of cement. Tied to 4-1/2" and squeezed with 30 sacks of cement to 500 lbs. Tied to 8-5/8" and squeezed with 25 sacks of cement at 300 lbs.

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
2978	2985		

RECEIVED
KCC DISTRICT #2
JUL 17 2006
WICHITA, KS

INVOICED
DATE 8/31/06
WEL. NO. 200706.0477

RECEIVED
AUG 30 2006

Remarks:

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

PKT