

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-01016-00-02  
Spot: S2NESENW Sec/Twnshp/Rge: 36-33S-6W  
3497 feet from S Section Line, 2979 feet from E Section Line  
Lease Name: GERBERDING Well #: 2  
County: HARPER Total Vertical Depth: 3350 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 200 W DOUGLAS AVE., STE 520  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4457		
SURF	8.625	320		
T1	2.875	4400		

\$ 108.88

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/24/2006 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: 2 sxs on CIBP; 35 sxs @ 1050'; 35 sxs @ 950'; circ cmt 370-0; CIBP set before plugging crew arrived.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/24/2006 3:30 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The plugging crew dumped 2 sacks of cement on CIBP. Perforators shot holes at 1050', 650', and 370'. Ran tubing to 1054' and spotted 35 sacks of cement. Pulled tubing to 650' and spotted 35 sacks of cement. Pulled tubing to 370' and circulated cement to surface inside and outside of 5-1/2" casing. Pulled tubing from well. Tied on swedge and squeezed 75 sacks of cement. SI 300 lbs.

Gressel Cement and Acid  
235 sacks of 60/40 posmix with 4% gel

**Perfs:**

Top	Bot	Thru	Comments
4457	4463		
4365			
3788	3792		
3550			
3502	3504		

RECEIVED  
KCC DISTRICT #2  
JUL 31 2006  
WICHITA, KS

INVOICE  
DATE 8/31/06  
200706047.8

RECEIVED

AUG 30 2006


KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)



