

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21553-00-00
Spot: SWNE Sec/Twnshp/Rge: 15-31S-7W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MOLLOHON Well #: 1-15
County: HARPER Total Vertical Depth: 4812 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 200 W DOUGLAS AVE., STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	265	0	190 SX CMT.

\$ 156.39

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/17/2006 2:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: TODD ALLAM Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 35 sxs @ 1225'; 35 sxs @ 800'; 35 sxs @ 315'; 25 sxs @ 60'; and 15 sxs in rathole.

Plugging Proposal Received By: JEFF KLOCK
Date/Time Plugging Completed: 06/17/2006 4:00 AM

Witness Type: NONE
KCC Agent: STEVE VANGIESON

RECEIVED
KCC DISTRICT #2

Actual Plugging Report:

The drill pipe was ran open end to 1225' and 35 sacks of cement was spotted. The drill pipe was pulled to 800' and 35 sacks of cement was spotted. The drill pipe was pulled to 315' and 35 sacks of cement was spotted. The drill pipe was pulled to 60' and cement was circulated to surface. The rathole was circulated with 15 sacks of cement.

60/40 posmix with 4% gel

Perfs: JUL 3 1 2006
WICHITA, KS

INVOICED
DATE 8/31/06
NO. 2007060478

RECEIVED
AUG 30 2006
KCC WICHITA

Remarks:
Plugged through: DP

District: 02

Signed [Signature]
(TECHNICIAN)

[Signature]

PCT