

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Grady Bolding Corporation Address: P.O. Box 486 Ellinwood, Ks. 67526 Phone: (620) 564-2765 Operator License #: 7383

API Number: 15-051-23,034-00-00 Lease Name: Arrbruster Well Number: 4

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): NE SE SE 990 Feet from North / South Section Line

The plugging proposal was approved on: (Date)

330 Feet from East / West Section Line

by: Herb Deines (KCC District Agent's Name)

Sec. 17 Twp. 12 S. R. 20 East X West

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

County: Ellis

Producing Formation(s): List All (if needed attach another sheet) Depth to Top: Bottom: T.D.

Date Well Completed: 5-29-82 Plugging Commenced: 8-11-06 Plugging Completed: 8-15-06

Show depth and thickness of all water, oil and gas formations.

Table with 2 main columns: Oil, Gas or Water Records and Casing Record (Surface Conductor & Production). Rows show formation details like 8-5/8" and 4-1/2" casing.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Plugged off bottom with sand to 3840' and 4 sacks cement. Casing Parted @1250' Pumped 50 sacks cement @1250'. pulled up to 950', pumped 35 sacks cement, pulled up to 250', pumped 25 sacks cement, tied onto 8-5/8", pumped 200# hulls and 20 sacks cement. 60/40 pos, 2% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Grady Bolding Corporation

State of Kansas County, Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

RECEIVED AUG 29 2006 KCC WICHITA

SUBSCRIBED and SWORN TO before me this 28th day of August 20 06

(Signature) Irene Herzberg Notary Public My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PAT