

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Kermit Schmidt Oil Operations
Address: 308 W. Lane McPherson, Ks. 67460
Phone: (620) 242 7535 Operator License #: 6523
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Dave Wertz (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-173-20273-00-00
Lease Name: Harant
Well Number: 1
Spot Location (QQQQ): 100' N NE - NE - NW
220 5130 Feet from North / South Section Line
2310 3080 Feet from East / West Section Line
Sec. 14 Twp. 26 S. R. 2 East West
County: Sedgwick
Date Well Completed: 11-12-80
Plugging Commenced: 8-14-06
Plugging Completed: 8-16-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	222'	None
				5-1/2"	3176'	1998'
				4-1/2"	2500'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 2940' and 4 sacks cement. Cut casing loose @1998', pulled up to 275', pumped 140 sacks cement and circulated to surface. Layed rest of casing down. Used 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Kermit Schmidt Oil Operations
State of Kansas County: Rice ss.

RECEIVED
AUG 31 2006
KCC WICHITA


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 30th day of August, 2006

Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC
ACT
9/15/06
Per
Pigs
edited
GPS

KCC 9/1/06
Per
RBDMS

PST