

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: August 21, 2006 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
3392-3462 Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 185-22748-0000

Lease Name: Hitz

Well Number: #3

Spot Location (QQQQ): C - NE - NW - SW
2310 Feet from North / South Section Line

4290 Feet from East / West Section Line

Sec. 7 Twp. 22 S. R. 12 East West

County: Stafford

Date Well Completed: 1/91

Plugging Commenced: 8/22/06

Plugging Completed: 8/22/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	276	8 5/8	276	
	Production	Surface	3811	5 1/2	3811	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech perforate 2 holes @ 750', TIH w/2 3/8" open-ended tbg = 3700'. RU Quality Oilwell Cementing. Mix & pump 15 sx gel spacer, follow up w/50 sx 60/40 Poz, 6% gel, 100# hulls, pull tbg up to 750', mix & pump 80 sx cement, circ up 5 1/2" csg, shut in 5 1/2" csg. Circ 150 sx up 8 5/8" csg. TOH w/tbg. Top off w/10 sx, Total 290 sx. Job complete @ 2:15 pm. Witnessed by Richard Lacey w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.


State of Kansas County, Sedgwick, ss.

Susan Sears (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Susan Sears

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 30th day of August, 20 06

Susan Brady My Commission Expires: 11-4-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 05 2006
KCC WICHITA

PKT