

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: August 21, 2006 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet) 3689-3691, 3646-3649 Depth to Top: Bottom: T.D.

API Number: 15-185-12743-0000

Lease Name: Harms W KCC 9/6/06 Pkt

Well Number: #4 PER CP-23

Spot Location (QQQQ): C - NW - NW 4620 Feet from North / South Section Line

4620 Feet from East / West Section Line

Sec. 18 Twp. 22 S. R. 12 East West

County: Stafford

Date Well Completed: 3/43

Plugging Commenced: 8/21/06

Plugging Completed: 8/21/06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes data for Surface and Production layers.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Tag TD @ 2135', open ended 2 3/8" tbg ran to 2130'. RU Quality Oilwell Cementing. Mix & pump 70 sx 60/40 Poz, 6% gel, 300# hulls, spot @ 2130', pull tbg to 750', mix & pump 80 sx, circ cement to surface. TOH w/tbg, hook up to 7" csg. Mix & pump 30 sx, 800 #, shut in. Hook up to 13" csg, mix & pump 70 sx, 150#, shut in. Job finished @ 12:30 pm. Witnessed by Richard Lacey, with KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.


State of Kansas County, Sedgwick, ss.

Susan Sears

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Susan Sears

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 30th day of August, 2006

Susan Brady Notary Public My Commission Expires: 11-4-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED SEP 05 2006 KCC WICHITA

Pkt