

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

Form CP-4
 December 2003
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil DH Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: August 21, 2006 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

3559-61, 3563-69, 3508-12, 3482-86 Depth to Top: _____ Bottom: _____ T.D. _____
 3467-71, 3451-55, 3404-08, 3391-3393 Depth to Top: _____ Bottom: _____ T.D. _____
 3386-88, 3378-80, 3320-29, 3338-51 Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-11228-0000

Lease Name: Karl Teichmann OWWO

Well Number: #3

Spot Location (QQQQ): _____ - C - NE - SW
1980 Feet from North / South Section Line

3300 Feet from East / West Section Line

Sec. 8 Twp. 22 S. R. 12 East West

County: Stafford

Date Well Completed: 6/48

Plugging Commenced: 8/17/06

Plugging Completed: 8/17/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	278	8 5/8"	278	
	Production	Surface	3669	5 1/2"	3669	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Allied Cementing. Mix & pump 50 sx 60/40 Poz, 6% gel. Spot @ 2950', pull tbg to 750', mix & pump 250 sx, circ cmt up 5 1/2" csg & up 8 5/8" surface pipe. TOH w/tbg. Top off w/50 sx. Used 350 sx 60/40 Poz, 6% gel, 150# hulls. Job completed @ 4:30 pm. Witnessed by Richard Lacey w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202


Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Susan Sears (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED
 SEP 06 2006
 KCC WICHITA



(Signature) Susan Sears

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 1st day of September, 20 06

Susan Brady My Commission Expires: 11-4-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT