

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior Inc.  
Address: P.O Box 399, Garden City Ks. 67846  
Phone: (620 ) 272 - 1023 Operator License #: 4058  
Type of Well: oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 8/2/06 (Date)  
by: Pat (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3706' Bottom: \_\_\_\_\_ T.D. 3764'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-23904 - 00 - 00  
Lease Name: Martin Dreiling  
Well Number: #3  
Spot Location (QQQQ): C - S2 - S2 - SW  
330' Feet from  North /  South Section Line  
3894' Feet from  East /  West Section Line  
Sec. 36 Twp. 14S S. R. 19W  East  West  
County: Ellis  
Date Well Completed: 7/1/84  
Plugging Commenced: 8/9/06  
Plugging Completed: 8/9/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil and gas	320'	Surface	85/8	320'	0
		3762'	Surface	51/2	3762'	0


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg to 3620', Allied hooked up and pumped 100 sx 60/40 poss with 300# hulls. Pulled tbg to 2000', Allied hooked up and pumped 100sx with 300# hulls, Pulled tbg to 1350', Allied hooked up and pumped 90 sx 60/40 pos. Pulled tbg to 750', Allied hooked up and pumped 35sx 60/40 pos. Cement circulated to surface. Hooked to surface pipe. Pumped 5sx, pressured to 500# and held. Topped 51/2 off with 5sx.

Name of Plugging Contractor: Allied cementing Western well service License #: 32128  
Address: \_\_\_\_\_

Name of Party Responsible for Plugging Fees: American Warrior Inc.  
State of Kansas County, Finny, ss.  
Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KCC PKT 9/8/06  
32128 PERCP213  
**RECEIVED**  
SEP 07 2006  
KCC WICHITA



(Signature) [Signature]  
(Address) P.O. Box 399 Garden City Kansas 67846

SUBSCRIBED and SWORN TO before me this 5 day of Septemer, 20 06  
Erica Kuhlmeier My Commission Expires: 09-12-09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT