

KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA STATE OFF. BUILDING  
130 S MARKET ROOM 2078  
WICHITA KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-073-22191-00-00

LEASE NAME Harshman

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 3  
NESESE

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 8 TWP. 23 RGE. 13 (E) or (W)

COUNTY Greenwood

Date Well Completed 4-82

Plugging Commenced 7-27-06

Plugging Completed 7-27-06

LEASE OPERATOR Evans Oil, Inc.

ADDRESS PO Box 67 Lebo, KS 66856

PHONE # 204-37-2595 OPERATORS LICENSE NO. 6078

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-27-06 (date)

by Mike Heffern, District #3 (KCC District Agent's Name).

Is ACO-1 filed? NA If not, is well log attached? Yes

Producing Formation Mississippi Depth to Top 1797' Bottom 1804' T.O. 1826'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

SEP 07 2006

KCC WICHITA

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	50'	None
				4 1/2"	1826'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Spot plugs down 2 3/8" tubing as follows:  
8 BBL gel spacer, 20sxs @ 1700', Perforate 2 shots, 3.5 BBL gel spacer, 25sxs @ 800', 1 BBL gel spacer, Perforate 2 shots @ 150', 34sxs @ 150' to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Schankie Well Service, Inc. License No. 6470

Address 1006 SW Blvd, P O Box 397 Madison, KS 66860

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Evans Oil, Inc. Lebo, KS 66856

STATE OF Kansas COUNTY OF Greenwood, ss.

Randall Schankie

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Randall Schankie

(Address) PO Box 397 Madison, KS 66860



TO before me this 17th day of August, 2006

Carol R. Bolan  
Notary Public

My Commission Expires: 1-9-2009





**PRECISION WELL PERFORATORS**

P.O. BOX 401 CHANUTE, KS 66720  
620-431-1010 620-431-8055 cell

**INVOICE**

SCHANKIE WELL SERVICE  
BOX 397  
MADISON, KS 66860

DATE	CUST NO.	SALESPERSON	TERMS

QTY	DESCRIPTION
1619A	Harshman #3 07-27-06
	Perforate Well with (2) Shots at 800.0' at 150.0' so well can be properly plugged with cement
	THANK YOU!

**Please make checks payable to:**

Precision Well Perforators  
P.O. Box 401  
Chanute, KS 66720

Tax rate %  
SHIPPED

RECEIVED  
SEP 07 2006  
KCC WICHITA