

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02191-00-00

Spot: NENW

Sec/Twnshp/Rge: 20-19S-9W

660 feet from N Section Line,

1980 feet from W Section Line

Lease Name: PROFFITT

Well #: 2

County: RICE

Total Vertical Depth: 3256 feet

Operator License No.: 9292

Op Name: SCHECK, TIMOTHY DBA SCHECK OIL

Address: 225 MAIN

RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	5.5	3245		100 SX CMT
------	-----	------	--	------------

SURF	8.625	241		135 SX CMT
------	-------	-----	--	------------

\$ 105.82

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/28/2006 8:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: NONE

Date/Time Plugging Completed: 06/28/2006 12:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2850' and capped with 5 sacks of cement. Copeland Log perforated at 1200', 800', and 300'. Ran tubing to 1200' and pumped 35 sacks of cement. Pulled tubing to 800' and pumped 35 sacks of cement. Pulled tubing to 300' and circulated cement and 5 sacks of gel up the long string and surface casing. Topped off with 25 sacks of cement.

60/40 posmix with 4% gel

Copeland #C30599

Perfs:

Top	Bot	Thru	Comments
3122	3126		
2926	2930		

RECEIVED
KCC DISTRICT #2

JUL 14 2006

WICHITA, KS

INVOICE

DATE

8/31/06

INV. NO.

2007060477

RECEIVED

AUG 30 2006

Remarks:

KCC WICHITA

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)