

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02124-00-00
Spot: NENWSW Sec/Twnshp/Rge: 14-19S-9W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: MAES Well #: 7
County: RICE Total Vertical Depth: 3231 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 225 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3222		125 SX
SURF	8.625	190		150 SX

105.01

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2006 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 06/26/2006 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2900' and capped with 5 sacks of cement. Well squeezed from 1765' to surface. Ran tubing to 1150' and pumped 35 sacks of cement. Pulled tubing to 800' and pumped 35 sacks of cement. Pulled tubing to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland #C030598

Perfs:

Top	Bot	Thru	Comments
340	1765		

RECEIVED
KCC DISTRICT #2
JUL 14 2006
WICHITA, KS

RECEIVED
SEP 01 2006

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 9/5/06
INV. NO. 2007060484

PCT