

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-06354-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 25-18S-8W  
2267 feet from S Section Line, 3723 feet from E Section Line  
Lease Name: LANSING J R - A Well #: 11  
County: RICE Total Vertical Depth: 3182 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 225 MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3162		
SURF	8.625	300		

\$ 103.42

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2006 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed  
Plugging  
Method:

See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 07/10/2006 3:20 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded perforations to 2800' and capped with 5 sacks of cement. Perforated at 1050', 700', and 350'. Ran tubing to 1050' and pumped 35 sacks of cement. Pulled tubing to 700' and pumped 35 sacks of cement. Pulled tubing to 350' and circulated cement to surface. Came back on 7/11/2006 and retagged cement at 350' and pumped another 280 sacks of cement.

500 sxs 60/40 posmix with 4% gel

Copeland #C030547  
Log Tech #4581

RECEIVED  
KCC DISTRICT #2  
JUL 14 2006  
WICHITA, KS

RECEIVED  
SEP 01 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 9/5/06  
VV. NO. 2007060484

R

P169