

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02765-00-00
Spot: SESWNE Sec/Twnshp/Rge: 15-20S-10W
2973 feet from S Section Line, 1730 feet from E Section Line
Lease Name: KOENIG Well #: 3
County: RICE Total Vertical Depth: 3371 feet

Operator License No.: 32490
Op Name: SCHMIDT, TERRY D.
Address: 1325 OAKLANE
MCPHERSON, KS 67460

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 4.5 | 3368 | | |
| SURF | 8.625 | 210 | | |

\$ 109.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2006 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/02/2006 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Attempted to run sandline and bailer, but encountered blockage at 300'. Ran 1" tubing down to 2500' and hit solid plug. Well is believed to have been perforated at 2360' in the Tarkio shallow gas zone. Pulled to 2480' and pumped 40 sacks of cement. Perforated at 1300', 900', and 260'. Ran tubing back down to 1300' and pumped 35 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 260' and circulated cement to surface.

60/40 posmix with 4% gel
Copeland #C030596

Perfs:

| Top | Bot | Thru | Comments |
|------|-----|------|----------|
| 3371 | | | |
| 3058 | | | |

RECEIVED
KCC DISTRICT #2
JUL 14 2006
WICHITA, KS

RECEIVED
SEP 01 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
915106
2007060486

a

PT