

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24880-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 20-12S-20W
4950 feet from S Section Line, 1980 feet from E Section Line
Lease Name: NICHOLSON Well #: 7
County: ELLIS Total Vertical Depth: 3975 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	5.5	3974	0	w/100 sxs cmt	\$129.19
SURF	8.625	232	0	w/unknown sxs cmt	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2006 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAN WEINHOLD Company: GLM COMPANY Phone: (785) 483-1599

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well perforated at 1545' and circulated cement with 400 sxs.
Emergency plug with rig over the hole.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2006 5:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3900' - mixed and pumped 100 sxs cement.
Pulled up to 2800' - spotted 150 sxs cement with 500# hulls.
Pulled up to 1000' and circulated cement with 100 sxs.
POOH. Topped with 15 sxs.
Annulus full of cement.

Perfs:

INVOICED
DATE 9/7/06
2007060503

RECEIVED
SEP 06 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

replacement card ~~XXXXXXXXXX~~ 20-25-20W
 C N/2 NW NE

RANEY OIL CO
 LAWRENCE KS 66047

7 NICHOLSON

by ELLIS
 field DISTRICT 57 NORTH

API 15-051-24880

site 3-1/2 N OF ELLIS KS
 contr. EMPHASIS OIL OPER # 5

oper. ROGER WELTY

tr date 09/26/94

sp date 09/27/94

drig comp 10/03/94

card issued 12/19/94

last rev 07/15/96

ELV	KB, 2252 GL LOG	depth/datum
tops		1620 + 637
ANH		3294 - 1037
TOP		3524 - 1287
HEEB		3545 - 1288
TOR		3562 - 1305
LANS		3802 - 1545
BKC		3854 - 1597
MARM		3924 - 1667
ARB		3975 - 1718
RTD		

IP status

OIL, P 34 BO & 70 EWPD, MARM 3858-3866, 10/23/94
 CORR & INFO REL. 7/15/96 - CORR ELEV (WAS 2258
 KB, 2253 GL), IP, DATES, TOPS, CSG, ADDED COMP
 INFO
 NOTE, CORR & INFO REL 1/2/95 - CORR RTD (WAS
 3950) & CORR IP, WAS OIL WELL - TIGHT HOLE
 CSG. 8-5/8" 232 (ALT 2), 5-1/2" 3974 / 100 SX, DV TOOL
 AT 1545 / 400 SX
 NO CORES
 DST (1) 3858-3935 (MARM, ARB, W/STR PKR), / 30-30-
 30-60, 60' GIP, REC 30' CLEAN GSY OIL (10% G, 90%
 OIL), 30' OC GSY M (10% G, 10% OIL, 10% W, 70% M),
 120' W 1SIP 695# FSIP 700# 1FP 50# FFP 110#

(over)

COPYRIGHT 1996
 INDEPENDENT OIL & GAS SERVICE, INC
 WICHITA KANSAS