

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-02109-00-00

Spot: SEnwSE

Sec/Twnshp/Rge: 18-16S-13W

1650 feet from S Section Line, 3630 feet from W Section Line

Lease Name: LUERMAN

Well #: 1

County: BARTON

Total Vertical Depth: 3385 feet

Operator License No.: 30742

Op Name: PALOMINO PETROLEUM, INC.

Address: 4924 SE 84TH STREET
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3378	0	100 SX CMT
SURF	10	160	0	200 SX CMT

\$ 110.01

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/23/2005 8:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: EDWARD S. NEMNICH

Company: PALOMINO PETROLEUM, INC.

Phone: (620) 587-3361

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/31/2006 2:00 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3300' and dumped 5 sxs cement.
No stretch on casing.
Perforated at 1625' - 900' - 525'.
Ran tubing to 1600'.
Pumped 55 sxs 60/40 pozmix - 10% gel cement with 200# hulls.
Pulled to 825' and pumped 145 sxs cement with 300# hulls.
Did not circulate.
POOH. Pumped 280 sxs cement with 1000# hulls down casing.
Did not stay full. Cement settled at approximately 600'.
08/31/2006 - Topped off with 50 sxs cement. Cement circulated up annulus.

Perfs:

Top	Bot	Thru	Comments
3378		OH	

INVOICED
DATE 9/7/06
2007060504

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

RECEIVED

SEP 06 2006

KCC WICHITA

District: 04

Signed

Case Morris
(TECHNICIAN)

SEP 01 2006

Pkt

HINKLE OIL & FRANCO OIL

#1

LUERMAN

18-16-13W
SE NW SE

Contr.

BARTON

County

E 1936

Comm.

6-5-45

Comp.

6-26-45

IP

193 BOPD

Tops	Depth	Datum
ANHY	885	
LAN S	3135	
S CONG	3362	
ARB	3378	
TD	3385	

Casing

10" 160

5" 3378

200' OIH/2 hr

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

