

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-02134-00-01  
Spot: NWNESWNW Sec/Twnshp/Rge: 10-24S-18E  
3700 feet from S Section Line, 4520 feet from E Section Line  
Lease Name: RIGGS Well #: 3 F  
County: ALLEN Total Vertical Depth: 866 feet

Operator License No.: 32851  
Op Name: L & G PETROLEUM OPERATING, LLC  
Address: 1000 CAMINO DEL OESTE  
BAKERSFIELD, CA 93309

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	6.25	865	0	
L2	5.25	866	0	
SURF	8.25	576	0	

\$ 35.00

Well Type: EOR UIC Docket No: E09017.10 Date/Time to Plug: 06/27/2006 9:30 AM  
Plug Co. License No.: 9312 Plug Co. Name: EQUINOX OIL COMPANY  
Proposal Rcvd. from: RANDY STANLEY Company: L & G OIL COMPANY Phone: (661) 832-7417

Proposed Plugging Method: THIS WELL WAS DRILLED IN 1923. IT IS BELIEVED THAT THE WELL CONSISTS OF 8 1/4" CASING TO 576' THAT HAS BEEN CEMENTED IN FROM BOTTOM TO TOP. INSIDE THE 8 1/4" CASING IS A 6 1/4" LINER TO 865' AND INSIDE THAT A 5 1/4" LINER TO 866'. IT IS THOUGHT THAT ALL CASINGS ARE CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO PERFORATE THE CASINGS TO INSURE CEMENT FLOW IN THE BORE AND TO CIRCULATE THE 5 1/4" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/27/2006 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE CASINGS WERE PERFORATED AT 500' AND ALSO PERFORATED AT 200'. 1" PIPE WAS RAN INTO THE 5 1/4" CASING TO 862'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 5 1/4" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 81 SACKS OF CEMENT WITH 6% GEL WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED  
KCC DISTRICT #3

AUG 23 2006 CPT

CHANUTE, KS

RECEIVED  
SEP 07 2006  
KCC WICHITA

INVOICED  
DATE 9/8/06  
NO. 2007060515

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

PKT