

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20223-00-00  
Spot: SEWSE Sec/Twnshp/Rge: 2-5S-22W  
1678 feet from S Section Line, 1764 feet from E Section Line  
Lease Name: WEILERT-WALTERS Well #: 2  
County: NORTON Total Vertical Depth: 3500 feet

Operator License No.: 9559  
Op Name: PATTERSON, JERRY DBA JERRY PATT  
Address: PO BOX 307  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3498	0	w/unknown sxs cmt
SURF	8.625	230	0	w/unknown sxs cmt

\$ 113.75

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/31/2006 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JERRY PATTERSON Company: JERRY PATTERSON OIL Phone: (785) 689-4897

Proposed Plugging Method: Ordered out 170 sxs Swift Multi Density Cement with 500# hulls.  
No squeeze records. Perforate at 900' and 1750'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/31/2006 12:10 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Perforated at 1750' and 900' - two holes each.  
Ran tubing to 2034'. Swift pumped 90 sxs SMD with 200# hulls.  
PTOH. Swift squeezed with 20 sxs cement and 150 # hulls.  
Max. P.S.I. 500#. S.I.P. 200#.  
Hooked up to backside and pumped 40 sxs cement with 150# hulls.  
Max. P.S.I. 400#. S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
3498	3500	OH	

INVOICED  
DATE 9/8/06  
200-7060517

RECEIVED  
SEP 07 2006  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.  
Plugged through: TBG

District: 04

*MD*

Signed Richard Williams  
(TECHNICIAN)

SEP 05 2006

*PCT*