

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20262-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 2-5S-22W
1977 feet from S Section Line, 2331 feet from E Section Line
Lease Name: WEILERT-WALTERS Well #: 3
County: NORTON Total Vertical Depth: 3504 feet

Operator License No.: 9559 •
Op Name: PATTERSON, JERRY DBA JERRY PATT
Address: PO BOX 307
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3500	0	w/unknown sxs cmt
SURF	8.625	210	0	w/unknown sxs cmt

\$ 113.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2006 12:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JERRY PATTERSON Company: JERRY PATTERSON OIL Phone: (785) 689-4897

Proposed Plugging Method: Ordered out 275 sxs Swift Multi Density Cement with 600# hulls.
Fluid 400' from surface.
No squeeze records. Perforate at 1750' and 900'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2006 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated at 1750' and 900' - two holes each.
Ran tubing to 2034'. Swift pumped 120 sxs cement with 200# hulls - cwc.
PTOH. Squeezed 5 1/2" casing with 90 sxs cement and 300# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to backside and pumped 45 sxs cement with 100# hulls.
Max. P.S.I. 200#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3500	3504		OH
3484	3490		
3389	3391		
3320	3330		
3301	3304		

INVOICED
DATE 9/8/06
2007060517

RECEIVED
SEP 07 2006
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

SEP 05 2006

PJT