

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05128-00-01  
Spot: SWSESW Sec/Twnshp/Rge: 31-13S-19W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: G E RIEDEL Well #: 11  
County: ELLIS Total Vertical Depth: 3872 feet

Operator License No.: 31021  
Op Name: CASTELLI EXPLORATION, INC.  
Address: 6908 N.W. 112TH  
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	3748	0	w/90 sxs cmt
PROD	7	3842	0	w/120 sxs cmt
SURF	10.75	500	0	w/325 sxs cmt

\$125.84

Well Type: SWD UIC Docket No: D15333.0 Date/Time to Plug: 08/28/2006 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: DAVID FUNK Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-9405

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/30/2006 11:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

08/28/2006 - Witnessed by Case Morris  
Ran tubing to 1820' - pumped 460 sxs 60/40 pozmix - 10% gel with 1000# hulls.  
Pumped 100 sxs 60/40 pozmix - 6% gel with 4% c.c. - did not circulate.  
POOH. Let set overnight.  
08/29/2006 - Witnessed by Case Morris  
Ran in tubing - did not tag cement. POOH.  
08/29/2006 - Witnessed by Marvin Mills  
Put in 400 bbls. Drilling mud filled hole to top. Pumped 40 sxs at 1658'.  
Let set overnight.  
08/30/2006 - Witnessed by Marvin Mills  
Ran tubing to 1125' - spotted 25 sxs.  
Pulled tubing to 850' - cwc - 160 sxs with 600# hulls.  
Tied onto backside - pumped 50 sxs with 500# S.I.P.  
Topped off casing with 10 sxs cement.

**INVOICED**  
DATE 9/8/06  
WV. NO. 2007060511

RECEIVED  
SEP 07 2006  
KCC WICHITA

Remarks: QUALITY CEMENTING - TICKET #1113.

Plugged through: TBG

District: 04

*170*

Signed *Marvin Mills*  
(TECHNICIAN)

SEP 06 2006

*ACT*

31-13-19  
SW SE SW

TEXAS COMPANY #11 REIDEL

Contr. STICKLE DRLG ELLIS County

E 2232RB Comm. Comp. 2-28-58 IP 25 BOPD

Tops	Depth	Datum
Anh.	1068	+1164
HEEB	3483	-1251
TOR	3504	-1272
LANS	3524	-1292
ARB	3838	-1606
TD	3872	-1640

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

Casing  
10" 491  
7" 3842

DST 3847-72/1 HR, 250' G,  
75' OCM, 678' O, BHP 985#  
DC: CO TD: SWB 35 BO, TR WTR/  
5 HRS: SWB 18 BO, TR WTR/3 HRS

**MAOICED**

IRVIN POOL

