

KANSAS CORPORATION COMMISSION
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
 Please TYPE Form and File ONE Copy

Form CP-1
 September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - ~~15~~ - 125 - 20205 - 0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: KDOT (Owner / Company Name) KCC License #: 102 (Operator's)

Address: 750 E 15 City: Liberal

State: KS Zip Code: 67901 Contact Phone: (620) 624 - 4451

Lease: Heatherington Well #: 1-7 Sec. 7 Twp. 35 S. R. 33 East West

S2 - SW - NW SW Spot Location / QQQQ County: Seward

1500 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 1630' Cemented with: 900 Sacks

Production Casing Size: 5 1/2 Set at: 6409' Cemented with: 215 Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 2890 (G.L. / K.B.) T.D.: 6845 PBTD: 6365 Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

RECEIVED
AUG 21 2006
KCC WICHITA

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Michael Carlile

Phone: (620) 629 - 0852

Address: PO Box 2436 City / State: Liberal KS

Plugging Contractor: Sargent & Horton KCC License #: 31151 (Contractor's)

Address: Tyrone OK Phone: (580) 651 - 3005

Proposed Date and Hour of Plugging (if known?): well plugged 8-29-06 apb kcc.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-17-06 Authorized Operator / Agent: Michael Carlile (Signature)

RECEIVED
AUG 21 2006
KCC WICHITA

2nd pump 400 # hulls + 50 SKs cement and displace to 6200'
2nd Free pt. 5 1/2" casing - at shoot-off depth pump 50SK
emt.
3rd pull 5 1/2 casing to 1660' - pump 50SK emt.
4th pull 5 1/2 casing to 840' " " "
5th 60' - 0 pump. 20SK emt
60/40 Poz. mix 6% gel.

Steve Durrant
620-225-8888
Dist. mgr.

J & R Sand Company, Inc
P.O. Box 2436
Liberal, Kansas 67905-2436
620-624-8439

To Whom It May Concern:

The well in which we want to plug has been condemned by KDOT. We are the general contractor on the job which the well is located. We know asphalt not oil wells. Please let me know if there is anything else we need to do.

Thank you,



Michael Carlile

RECEIVED
AUG 21 2006
KCC WICHITA