

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

CORRECTED

Lease Operator: Hess Oil Company

Address: P. O. Box 1009, McPherson, KS 67460

Phone: (620) 241-4640 Operator License #: 5663

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 4471' Bottom: 4481' T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API Number: 15 - 195-21,964-00-00

Lease Name: Giess

Well Number: B-1

Spot Location (QQQQ): Approx - E/2 - SE - NE

3390 Feet from North South Section Line

330 Feet from East West Section Line

Sec. 26 Twp. 15 S. R. 25 East West

County: Trego 5-1 KCC Perc 2/3

Date Well Completed: 4-19-88 2/10/06 PRT

Plugging Commenced: 8-10-06

Plugging Completed: 8-23-06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include surface and production data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

(Failed attempt: Pumped cement down inside of 5-1/2" - 50 sacks with 400# hulls, then 3 sacks gel spacer, but could not pump any more.) Pumped 40 sacks 60/40 pozmix down outside of 5-1/2" on 8-10-06 to fill to surface. On 8-23-06, pushed in tubing to 2025' to wash out 5-1/2". Pulled tubing up to 1995' and pumped 135 sacks 60/40 pozmix, 10% gel, 1 sack hulls through tubing to fill up inside 5-1/2". Finished by pulling tubing out, and pumping in 15 sacks more to fill 5-1/2" to surface.

Name of Plugging Contractor: Hess Oil Company License #: 5663

Address: same

Name of Party Responsible for Plugging Fees: Hess Oil Company

State of Kansas County, McPherson, ss.


Bryan Hess, President

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Bryan Hess (Address) same

SUBSCRIBED and SWORN TO before me this 6th day of September, 2006

Carol A. Nickel Notary Public My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED SEP 07 2006 KCC WICHITA

PRT