

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R.P. Nixon Operations, Inc.
Address: 207 West 12th Street
Phone: (785) 628-3834 Operator License #: 5252
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3.17.06 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L/KC Depth to Top: 3284' Bottom: 3509' T.D. 3598'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-21,394-00-00
Lease Name: Pete
Well Number: 1
Spot Location (QQQQ): SE - NE - SE -
3630 Feet from North / South Section Line *KCC*
330 Feet from East / West Section Line *9/11/06*
Sec. 4 Twp. 14 S. R. 17 East West *PCT*
County: Ellis
Date Well Completed: 10-24-77 1-18-78 *per CP213*
Plugging Commenced: 3.21.06 *per RBoms +*
Plugging Completed: 3.21.06 *ACO-1*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	206'	none
				4 1/2"	3588'	none


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated casing at 1850' & 1225', 2 shots/foot. Ran tubing down to 2200'. Tied onto 8 5/8" and pumped 25 sacks 60/40 Pozmix, 10% gel.
Cement circulated out the 4 1/2" casing. Tied on to tubing and pumped 110 sacks same cement with 500# hulls. Cement circulated.
Pulled tubing from well and tied on to 4 1/2" casing and pumped 65 sacks of same cement w/o hulls. Maximum pressure was 700#.
Instant shut-in pressure 600#. Witnessed by KCC man Jay Pfeifer.

Name of Plugging Contractor: Express Well Service License #: 6426
Address: Box 19 Victoria, KS 67671
Name of Party Responsible for Plugging Fees: R.P. Nixon Oper., Inc.
State of Kansas County, Ellis, ss.
Dan A. Nixon (Employee of Operator) or (Operator) on above-described well, being first duly

RECEIVED
SEP 08 2006
KCC WICHITA

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) 207 West 12th Street Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 6th day of September, 20 06

[Signature] My Commission Expires: 3.12.2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PCT