

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.
Address: P.O Box 399, Garden City Ks. 67846
Phone: (620) 272 - 1023 Operator License #: 4058
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/25/00 (Date)
by: Pat (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3785' Bottom: 3980' T.D. 4172'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-01024 -00-00
Lease Name: Blazier
Well Number: 1
Spot Location (QQQQ): C - NE - SW - SE
990' Feet from North / South Section Line
1650' Feet from East / West Section Line
Sec. 21 Twp. 790' S. R. 25 East West
County: Graham
Date Well Completed: 7/8/55 (spud) KCC 9/11/06
Plugging Commenced: 7/31/06 PKT
Plugging Completed: 7/31/06 per CP2/3
RB Dms

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	oil and gas	238'	surface	85/8	238'	0
		4172'	surface	51/2	4172'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech perf 2175', 4spf, 1400', 4spf, 290' 4spf. Ran tbg to 2480'. Swift hooked up and pumped 55sx plug, Pulled tbg to 1500', Swift hooked up and pumped 75sx plug. Pulled tbg to 500', Swift hooked up and pumped 60sx Circulated 10sx to pit. Pulled tbg. Hooked up to 51/2 pumped 40sx cement coming out 85/8. Cut off 6' below surface and capped. 230sx 60/40/pos cement.

Name of Plugging Contractor: Swift Services inc KC Well Service, Inc License #: 33555 32302
Address: P.O. box 466 Ness City Kansas 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.
Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]
(Address) P.O. Box 399 Garden City Kansas 67846

SUBSCRIBED and SWORN TO before me this 6 day of September, 20 06
Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

PKT