

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: OIL EOR Docket #: E24173.4  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: KCC 9/11/06 PKT Per CP2/3 (Date)

by: \_\_\_\_\_ (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

LKC 3806-14, 3836-42, 3848-56, Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

3882-88, 3938-42, 3958-64, Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

3978-84, 3998-4006 Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 065-20251-0001

Lease Name: Gano SE Unit SE Gano Unit

Well Number: 2-3

Spot Location (QQQQ): SE - SE - SW -

330 Feet from  North /  South Section Line

2970 2790 Feet from  East /  West Section Line

Sec. 12 Twp. 10 S. R. 24  East  West

County: Graham

Date Well Completed: 12/69 (original)

Plugging Commenced: 8/24/06

Plugging Completed: 8/24/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	190	8 5/8	190	0
	Production	Surface	4056	4 1/2	4056	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH with 2 3/8" tbg to 2200'. RU Swift Services. Pumped 75 sacks SMD to circ cement to surface. TOH w/tbg. Tied onto 8 5/8". Pressured to 300#, held. Tied onto 4 1/2" csg. Pumped 125 sacks SMD, 300# hulls, max pressure 300#, ISIP 100#. Plugged at 3:30 pm. Witnessed by Rich Williams w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202


Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Susan Sears, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Susan Sears

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



and SWORN TO before me this 7th day of September, 20 06

Susan Brady My Commission Expires: 11-4-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC 9/11/06  
PKT Per CP2/3

KCC 9/11/06  
PKT Per CP2/3

RECEIVED  
SEP 11 2006  
KCC WICHITA

PKT