

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Berexco, Inc.

Address: P.O. Box 20380, Wichita, KS 67208

Phone: (316) 265-3311 Operator License #: 5363

Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 26 July 2006 (Date)

by: Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

n/a Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 175-22052-00-00

Lease Name: Wanda Mae

Well Number: #1

Spot Location (QQQQ): C - SE - SW - SE
330 Feet from ☐ North / ☒ South Section Line

1650 Feet from ☒ East / ☐ West Section Line

Sec. 34 Twp. 31 S. R. 31 ☐ East ☒ West

County: Seward

Date Well Completed: 26 July 2006

Plugging Commenced: 26 July 2006

Plugging Completed: 27 July 2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	30 feet	20" conductor	30'	none
		surface	1726'	8-5/8" surf.	1726'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 100 sacks cement through drill pipe at 3205 feet, 50 sacks cement at 1781 feet, 40 sacks cement at 661 feet, 20 sacks cement from 62 feet to surface. Filled rat hole with 60 sacks cement and filled mouse hole with 30 sacks cement.
Cement blend: 60/40 POZ, 6% gel.


Name of Plugging Contractor: Berexco, Inc. with Allied Cementing Equipment License #: 5363 5147

Address: P.O. Box 20380, Wichita, KS 67208

Name of Party Responsible for Plugging Fees: Berexco Inc.

State of KS County, Sedgwick, ss.

Richard R. Smith, Engineering Technician (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Richard R. Smith

(Address) 2020 No Bramblewood, Wichita, KS 67208

SUBSCRIBED and SWORN TO before me this 5th day of September, 2006

Diana E Plotner My Commission Expires: Aug 10, 2007
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 07 2006
KCC WICHITA