

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gusher OII
Address: 460 Avenue E Bushton, Ks. 67427
Phone: (620) 562-3352 Operator License #: 30010 33748
Type of Well: Oil Docket #: KCC PRT 9118106
PER OPS 213
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Greg Evers (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-053-20,852-00-00
Lease Name: Roifs Farms
Well Number: 2
Spot Location (QQQQ): _____ SW/4
1215 Feet from North / South Section Line
3973 Feet from East / West Section Line
Sec. 33 Twp. 17 S. R. 9 East West
County: Ellsworth
Date Well Completed: _____
Plugging Commenced: 8-28-06
Plugging Completed: 8-30-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	347'	None
				4-1/2"	3231'	1300'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3180' and 5 sacks cement. Cut casing loose @1300', pulled up to 1200', purped 200# hulls and 35 sacks cement, pulled up to 850', purped 35 sacks cement, pulled up to 40' and circulated 120 sacks cement to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Gusher OII

State of Kansas County, Rice ss.

Mike Kelso

(Employee of Operator) or (Operator) on above-described well, being first duty

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Ks. 67524

SUBSCRIBED and SWORN TO before me this 13th day of September, 20 06

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 207B, Wichita, Kansas 67202

RECEIVED
SEP 15 2006
KCC WICHITA

KCC PRT
9118106
PER OPS
FTGS

prt