

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

03450-00-00

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: verbal approval (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3381' Bottom: 3396' T.D. 3396'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-97,574
Lease Name: Hall B
Well Number: #2 SW NW NW
Spot Location (QQQQ): _____ - NW - SE - SW
4290' Feet from North / South Section Line
4950' Feet from East / West Section Line
Sec. 26 Twp. 11 S. R. 17 East West
County: Ellis
Date Well Completed: 11/37
Plugging Commenced: 8/28/06
Plugging Completed: 8/28/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4	1120'	
				7	3381'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf'd 575' & 1115'. FL - 100' FS. TIH w/tbg. Tagged btm at 3200'. RU Allied. Spotted 30 sx cmt w/150# hulls on btm w/39 sx gel on top.
Pulled tbg to 1150' & spotted 30 sx cmt. Pulled tbg to 600' and circ. cmt to surf. w/100 sx cmt w/350# hulls. TOH w/tbg. Connected to 7" csg and pumped 175 sx cmt and lost circ. on 10 3/4". Connected to 10 3/4" & 7" annulus and pumped 25 sx cement. Pressured up to 500#, SIP - 500#. Connected back to 7" and pumped 50 sx cmt. Used total of 435 sx 60/40 poz w/10% gel. Approved by Jay Pfiefer w/KCC.

Name of Plugging Contractor: Smoky Hills Well Service
Allied Cementing Co., Inc. License #: 32452

Address: P.O. Box 31, Russell, KS 67665-0031

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Sedgwick, ss.

Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 13th day of September

Michelle D. Henning
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 15 2006
KCC WICHITA

pat

WELL RECORD

LEASE Hall WELL NO. 2-B S. 26 T. 11 R. 17W
 COUNTY Ellis STATE Kansas ELEV. 1927'
 LOCATION 992.3'S - 330'E of NW Cor.
 DR. COMMENCED 10-26-37 DR. COMPLETED 11-29-37
 DRILLED BY Twin Drilling Co.
 INITIAL PROD. 2773 oil, 0 wtr. SOURCE OF RECORD Log
24 hrs. nat. T.D. 3396'

CASING RECORD				LOCATION
SIZE	WEIGHT	FEET.	DISPOSITION	
15 $\frac{1}{2}$ "		120'	Cem. w/ 120 sxs.	
10 $\frac{3}{4}$ "		1120'	Cem. w/ 400 sxs.	
7"		3381'	S.L.M. Cem. w/ 250 sxs.	

PRODUCTIVE HORIZONS							
NAME OF SAND	O. OF G.	PRELIM.	T.S.	T.O.	PEN.	DATUM	
<i>Lansing 313c</i> Top Simpson			3374				
Siliceous Lime	Oil		3381	3396	15'		
Best Pay 3382-86' Fair Pay 3391-96' 2750' fluid in 2 3/4 hrs. Fluid level 2750' also.							

WATER HORIZONS			
FORMATION	QUANTITY OF WATER	FROM	TO
Drilled w/ rotary.			

RECEIVED
 SEP 15 2006
 KCCO WICHITA

ALLIED CEMENTING CO., INC.

27968

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>8/28/06</u>	SEC. <u>6</u>	TWP. <u>11</u>	RANGE <u>17</u>	CALLED OUT <u>10:45 AM</u>	ON LOCATION <u>1:45 PM</u>	JOB START	JOB FINISH <u>4:30 PM</u>
LEASE <u>H/M</u>	WELL # <u>B-2</u>	LOCATION <u>Codel/ 9114/ct. 25 E.N</u>			COUNTY <u>Ellis</u>	STATE <u>K</u>	

OLD OR NEW (Circle one)

CONTRACTOR Spooky Hill

TYPE OF JOB Plug

HOLE SIZE _____ T.D. _____

CASING SIZE 7" DEPTH _____

TUBING SIZE 2 3/8" DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT

AMOUNT ORDERED _____

450 lb 60/40 10 Used 435 lb

39 lb gel 600 Holly

COMMON	<u>29</u>	@	<u>10.65</u>	<u>2779.65</u>
POZMIX	<u>174</u>	@	<u>5.80</u>	<u>1009.20</u>
GEL	<u>76</u>	@	<u>16.65</u>	<u>1265.40</u>
CHLORIDE		@		
ASC		@		
<u>Holls</u>	<u>6</u>	@	<u>25.00</u>	<u>153.00</u>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>533</u>	@	<u>1.90</u>	<u>1012.70</u>
MILEAGE	<u>SK/pt 1.09</u>			<u>1535.00</u>
				TOTAL <u>7754.99</u>

EQUIPMENT

PUMP TRUCK CEMENTER Bill

366 HELPER PAN

BULK TRUCK

396 DRIVER Bob-Brandon

BULK TRUCK

_____ DRIVER _____

REMARKS:

Tubing @ 3200' Spot 39 lb gel
Follow w/ 30 lb Cent w/ 150# HLL
pull to 1150 Spot 30 lb Cent w/ HLL
pull to 600 Circ Cent w/ 100 lb
pull Tubing pump down 7" w/ 225 lb
w/ 150# HLL
pump down Ann w/ 25 lb press to 500'

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 720.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 32 mi @ 6.00 192.00

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 912.00



CHARGE TO: WES

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

RECEIVED

SEP 15 2006

KCC WICHITA

To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____