

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hess Oil Company

Address: P. O. Box 1009, McPherson, KS 67460

Phone: (620) 241-4640 Operator License #: 5663

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8-23-06 (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 4430' Bottom: 4433' T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-22,574-00-00

Lease Name: Bishop

Well Number: 2

Spot Location (QQQQ): NW - SE - SW -
990 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 30 Twp. 17 S. R. 24 East West

County: Ness

Date Well Completed: 6-25-84

Plugging Commenced: 9-5-06

Plugging Completed: 9-6-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
surface		717'	0'	8-5/8"	717'	none
production		4430'	0'	5-1/2"	4430'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran in 2" tubing to 4400', and pumped 40 sacks 60/40 pozmix, 6% gel, 100# hulls. Pulled tubing up to 1765', and pumped 25 sacks standard cement, 3% cc. Pulled tubing up to 1150', and pumped 50 sacks standard cement, 3% cc, then pulled tubing out and waited on cement to set. Connected to 5-1/2" and pumped 40 sacks 60/40 pozmix, 6% gel, 100# hulls, then displaced with water and pressured up to 1000#. Perforated 5-1/2" @ 1050', and pumped 150 sacks 60/40 pozmix, 6% gel. 5 bbls cement circulated to surface.

Name of Plugging Contractor: Hess Oil Company License #: 5663

Address: same

Name of Party Responsible for Plugging Fees: Hess Oil Company


State of Kansas County, McPherson, ss.

Bryan Hess, President (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Bryan Hess
(Address) same

SUBSCRIBED and SWORN TO before me this 11th day of September, 20 06



Carol A. Nickel My Commission Expires: 6-1-09
(Notary Public)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 18 2006
KCC WICHITA

PPT