

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Berexco, Inc.

Address: PO Box 723 Hays, KS 67601

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9-8-06 (Date)

by: Case Morris (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No, If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

TOR Depth to Top: 2888 Bottom: 2894 T.D. 3145  
PLATTS Depth to Top: 2819 Bottom: 2826 T.D. 3145  
L-KC O.H. Depth to Top: 2924 Bottom: 3145 T.D. \_\_\_\_\_

API Number: 15-167-07070-00-00

Lease Name: Rusch Seeley

Well Number: 2

Spot Location (QQQQ): E/2 - SE - SE  
330 Feet from  North /  South Section Line

330 Feet from  East /  West Section Line

Sec. 30 Twp. 14 S. R. 14  East  West

County: Russell

Date Well Completed: 11-2-40

Plugging Commenced: 9-6-06

Plugging Completed: 9-8-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	2924	7"	11-2-40	-----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Perftech shot 2 holes each @ 1400', 750', & 450'. Run open end tbg to 2000'. Fluid level 300' FS. Mix 125 sks 60/40 poz 10% gel w/ 400# hulls dwn tbg. Pull tbg to 1000'

Mix 300 sks 60/40 poz 10% gel w/ 300# hulls. Fld circ to surface, cmt didn't circ to surface. Pull tbg out of hole. Run sandline w/ 1 jt tbg tag cmt @ +/- 725'. Ran open end tbg to 738 - tag cmt

Set tbg @ 725' mix 100sks 60/40 poz 10% gel - circ cmt to surface in 7"x2-3/8 annulus. Pull tbg out. Tie to 7" csg - mix 80 sks cmt to top off & circ cmt to cellar.

Name of Plugging Contractor: Berexco Inc. License #: 5363

Address: PO Box 723 Hays, KS 67601


Name of Party Responsible for Plugging Fees: Dennis Kirmer

State of KS County, Ellis, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dennis Kirmer

(Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 13 day of September, 20 06

Shanna Miller My Commission Expires: 9-19-09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
SEP 18 2006  
KCC WICHITA

KCC AD  
9/20/06  
per  
CPI

PKT