

15-163-19127-00-00
WELL RECORD

Company Cities Service Oil Co. Well No. 2 Farm Reeder
 Location 1320' South and 330' East of Center Sec. 19 T. 8 R. 17W
 Elevation 1951 (1948 Gr.) County Rooks State Kansas
 Drlg. Comm. December 10, 1953 Contractor Lohmann-Johnson Drlg. Co., Inc.
 Drlg. Comp. December 28, 1953 Acid 1000 gals. 12-29-53
 T. D. 3379' Initial Prod. Physical Potential: 120 oil, no water, 24 hrs. (1-15-54)

CASING RECORD:

8-5/8" @ 240' con. 175 sz cement
 5-1/2" @ 3372' con. 175 sz cement

2-stage cementing collar at 1286' with
 300 sacks cement and 75 sacks Stratacrete.

FORMATION RECORD:

lime & shale	0-157
shale	240
shale & shells	1061
red bed	1268
anhydrite	1305
lime & shale	1910
shale & shells	1895
broken lime	2010
shale & lime	2155
lime & shale	2575
shale	2720
shale & lime	2870
lime & shale	3206
lime	3285
lime & shale	3334
lime	3374
lime	3374 RTD = 3372 SLM
lime	3379 T. D.

Gorr. Topeka	2854'	(-403)
Gorr. Heebner	3063'	(-1117)
Gorr. Dodge	3083'	(-1137)
Gorr. Lansing	3102'	(-1151)
Gorr. Arbuckle	3371'	(-61420)
Penetration	8'	
Total Depth	3379'	

Bailed 34 gals. oil/hr./10 hrs.

SLOPE TESTS (ACID BOTTLE):

500'	0°
1000'	0°
1500'	0°
2000'	0°
2500'	0°
3000'	0°

7-7/8" rotary hole.

2/16/54
1/15/54

Deepened 2-16-54
attached