

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20760-00-01
Spot: SWNWSE Sec/Twnshp/Rge: 2-27S-2E
1660 feet from S Section Line, 2454 feet from E Section Line
Lease Name: KRUG NORTH Well #: 1
County: SEDGWICK Total Vertical Depth: 3329 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	215		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/18/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DOUG LOUIS Company: KANSAS CORPORATION COMMIS Phone: (316) 630-4000

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/06/2006 11:38 AM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Perfs:

Well is located in Block 1, Lot 60, 13623 Candan Chase Street, Hawthorne Addition.

The well was bubbling and cement was drilled to 500'. Pumped 225 sacks of cement through tubing. Locked-up at 1,000 psi. Shut-in at 500 psi. The next day the well was still bubbling. The well was drilled out again to 1,000'. A gel spacer was pumped through the tubing at 1,000' to 500'. 150 sacks of UFC cement were pumped through the tubing from 500' to surface. There weren't any more bubbles. The 8-5/8" surface pipe was dugout from 5' below the basement grade and cut off. A steel plate was welded on to the top of the 8-5/8". The hole was back-filled.

RECEIVED
KCC DISTRICT #2
SEP - 7 2006
WICHITA, KS

Remarks: CONTROL #2007-0008-001

Plugged through: TBG

RECEIVED
SEP 11 2006
KCC WICHITA

District: 02

Signed David Wertz
(TECHNICIAN)

PKT