

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-01281-00-00
Spot: NESESE Sec/Twnshp/Rge: 17-34S-14E
850 feet from S Section Line, 400 feet from E Section Line
Lease Name: POWELL Well #: 18
County: MONTGOMERY Total Vertical Depth: 1289 feet

Operator License No.: 32596
Op Name: NEW DONNA LEE OIL COMPANY
Address: 221 FERN MEADOW DRIVE
BAKERSFIELD, CA 93308

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	2.375	1236		
PROD	4.5	1281		
SURF	8.625	20		20 ft is an estimate

\$ 41.89

Well Type: EOR UIC Docket No: E10949.1 Date/Time to Plug: 05/17/2006 8:00 AM
Plug Co. License No.: 33422 Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE
Proposal Rcvd. from: RICK HOUSEL Company: RICK'S WELL SERVICE Phone: (620) 336-2944

Proposed Plugging Method: Perforate pipe at selected intervals and then plug from bottom to top.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 05/17/2006 12:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The 2.375 inch liner (2nd production string), was perforated at 700 ft, 350 ft and 150 ft. A one inch cement string was then lowered to 1227 ft and the well plugged from bottom to top thru this one inch cement string. A total of 137 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 6 2006 AD
CHANUTE, KS

INVOICED
DATE 9/15/06
2007060534

Remarks:
Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN) PPT

Form CP-2/3
RECEIVED
SEP 14 2006
KCC.WICHITA