

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00623-00-00
Spot: SWNE Sec/Twnshp/Rge: 26-22S-36W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease Name: LIVENGOOD Well #: 1
County: KEARNY Total Vertical Depth: 2700 feet

Operator License No.: 32606
Op Name: DEVON ENERGY PRODUCTION COMP
Address: 20 N. BROADWAY
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
L1		2700		
PROD	7	2590	685	WITH 100 SX CMT
SURF	10.75	258		WITH 175 SX CMT

\$ 87.75

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/24/2006 4:00 PM
Plug Co. License No.: 31705 Plug Co. Name: HOLMAN, DENNIS LEE DBA H & K PLUGGING AND SALVAGE
Proposal Rcvd. from: JIM CONNERS Company: HOLMAN, DENNIS LEE DBA H & K Phone: (806) 665-2550

Proposed Plugging Method: CIBP @ 2600' WITH 4 SX CMT. PLUG AT 900' WITH 80 SX CMT. PLUG AT 290' WITH 100 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2006 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SLOTTED LINER FROM 2622-2700'. 1ST PLUG AT 2250' WITH 7" CIBP & 4 SX CMT. (TAGGED CMT AT 2255'). 2ND PLUG FREE POINT CASING, RECOVER 685' OF 7" CASING. TIH WITH 2 3/8" TUBING TO 882' & PUMP 120 SX CMT. WAIT ON CMT 2 HOURS. 3RD PLUG TIH WITH TUBING. TAG TOC @ 600'. PULL TUBING TO 283' & PUMP 100 SX CMT. 4TH PLUG PULL TUBING TO 63'. CIRCULATE CMT TO SURFACE WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2622	2700		

INVOICED

DATE 9/15/06
2007060528


RECEIVED

SEP 14 2006
KCC WICHITA

Remarks: USED CLASS A CMT BY H&K PLUGGING & SALVAGE.

Plugged through: TBG

District: 0



Signed

[Handwritten Signature]

(TECHNICIAN)

[Handwritten Signature]
PST