

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-00524-00-00  
Spot: NENESW Sec/Twnshp/Rge: 34-30S-33W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: EMMA HOPKINS Well #: 1  
County: HASKELL Total Vertical Depth: 2795 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PARKWA  
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		810		WITH 4 SX CMT \$ 90.84
PROD	6.625	2795	0	WITH 1000 SX CMT
SURF	10.75	693		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2006 8:00 AM  
Plug Co. License No.: 99994 Plug Co. Name: DOWELL SCHLUMBERGER  
Proposal Revd. from: MIKE HANEPHIN Company: EXXON MOBIL Phone: (281) 654-1929

Proposed Plugging Method: CIBP @ 810' WITH 4 SX CMT. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/06/2006 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

TUBING & RODS STUCK IN HOLE. CIBP @ 810' WITH 4 SX CMT. PERFORATE @ 686-688'. FILL 6 5/8" CASING FROM 0-688' WITH 100 SX CMT PLUS 80 SX CMT OUTSIDE CASING. NO CIRCULATION. PUMP 10 SX CMT DOWN BACKSIDE. PRESSURED UP & CASING HEAD STARTED TO LEAK. SHUT DOWN.

Perfs:

Top	Bot	Thru	Comments
2599	2718		


**INVOICED**  
DATE 9/15/06  
WT. NO. 2007060529

**RECEIVED**  
SEP 14 2006  
KCC WICHITA

Remarks: USED CLASS C CMT BY SCHLUMBERGER.

Plugged through: CSG

District: 01



Signed

Jim Holland PART III  
(TECHNICIAN)

Form

*[Handwritten signature]*  
PPT