

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21932-00-00

Spot: NENWSW

Sec/Twnshp/Rge: 14-20S-30W

2400 feet from S Section Line, 1160 feet from W Section Line

Lease Name: SCHWARTZ

Well #: 1-14

County: LANE

Total Vertical Depth: 4700 feet

Operator License No.: 3842

Op Name: LARSON ENGINEERING INC. DBA LAR

Address: 562 WEST STATE ROAD 4
OLMITZ, KS 67564

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 209 | | WITH 150 SX CMT |

\$ 152.75

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/29/2006 1:00 PM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: DON STRECKER

Company: MURFIN DRILLING CO., INC.

Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1360' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 50 SX CMT. 4TH PLUG AT 220' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

WitnessType: NONE

Date/Time Plugging Completed: 08/29/2006 3:45 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

Perfs:

1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1360' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 50 SX CMT. 4TH PLUG AT 220' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.


INVOICED
DATE 9/15/06
2007060532

RECEIVED
SEP 14 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Jim Holland PIRT III
(TECHNICIAN)

Form CP-2/3