

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20534-00-00
Spot: NESW Sec/Twnshp/Rge: 2-27S-17W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: FISHER Well #: 1
County: KIOWA Total Vertical Depth: 4714 feet

Operator License No.: 31938
Op Name: INDIAN OIL CO., INC.
Address: PO BOX 209 2507 SE US 160 HIGHWAY
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4709	2234	WITH 150 SX CMT
SURF	8.625	393		WITH 325 SX CMT \$153.21

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/08/2006 9:20 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: FLOYD CROCKETT Company: INDIAN OIL CO., INC Phone: (620) 886-3763

Proposed Plugging Method: SAND TO 4530' WITH 4 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/08/2006 10:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND BACK TO 4530' WITH 4 SX CMT. 1ST PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT. GOOD RETURNS. CEMENT CIRCULATED.

Perfs:


Top	Bot	Thru	Comments
4638	4648		
4618	4628		
4596	4600		

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
SEP 18 2006
KCC WICHITA
INVOICED
DATE 9/19/06
TEL. NO. 2007060548

District: 01



Signed Eric MacLaren
(TECHNICIAN)

Form CP-273

ACT