

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21407-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 19-25S-15W  
2310 feet from S Section Line, 330 feet from W Section Line  
Lease Name: GRIZZELL Well #: 1  
County: STAFFORD Total Vertical Depth: 4413 feet

Operator License No.: 5427  
Op Name: LAUCK, D.R. OIL CO., INC.  
Address: 221 S. BROADWAY, STE 400  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4412	2412	WITH 125 SX CMT
SURF	8.625	339		WITH 225 SX CMT <b>\$143.42</b>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2006 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4280' & 4 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/06/2006 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE = 1000'. SANDED TO 4280' & 4 SX CMT WITH DUMP BAILER.  
SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4335	4339		

RECEIVED  
SEP 18 2006  
KCC WICHITA


INVOICED

DATE 9/19/06  
2007060550

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: CSG

District: 0



Signed

Richard M. Lacey

(TECHNICIAN)