

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23207-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 10-10S-21W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: COOK Well #: 1
County: GRAHAM Total Vertical Depth: 3847 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	206		

\$ 125.03

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/13/2006 12:00 PM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: BRUNGARDT Company: PROSPECT OIL & GAS CORP. Phone: (785) 483-6266

Proposed Plugging Method: Ordered 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 08/13/2006 1:30 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3775' w/25 sxs.
2nd. Plug at 1730' w/25 sxs.
3rd. Plug at 915' w/100 sxs.
4th. Plug at 260' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED
SEP 18 2006
KCC WICHITA

INVOICED
DATE 9/19/06
2007060553

District: 04

Signed

Bruce D. Basye
(TECHNICIAN)

1720

Form CP-2/3

SEP 07 2006

PET