

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24533-00-00
Spot: S2SWNW Sec/Twnshp/Rge: 24-16S-24W
2241 feet from N Section Line, 600 feet from W Section Line
Lease Name: HORCHEM 24B Well #: 1
County: NESS Total Vertical Depth: 4647 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 244 | | WITH 170 SX CMT |

\$ 151.03

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/03/2006 6:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 1881' WITH 50 SX CMT. 2ND PLUG AT 1250' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 09/03/2006 8:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 1881' WITH 50 SX CMT. 2ND PLUG AT 1250' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL.

Plugged through: DP

RECEIVED
SEP 18 2006
KCC WICHITA

INVOICED
DATE 9/19/06
20070605.4

District: 01

RECEIVED
SEP - 6 2006
KCC Dodge City

Signed

Stephen J Pfeifer
(TECHNICIAN)

Form CR-213

PKT