

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20949-00-00
Spot: NWSENE Sec/Twnshp/Rge: 13-31S-5E
3440 feet from S Section Line, 1065 feet from E Section Line
Lease Name: DRAKE Well #: 3
County: COWLEY Total Vertical Depth: 3048 feet

Operator License No.: 5495
Op Name: MCPHERSON, BILL DBA MCPHERSON
Address: 15256 112TH RD
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3043		100 SX
SURF	8.625	170		

\$ 99.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2006 4:00 PM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL DBA MCPHERSON DRILLING CO.
Proposal Rcvd. from: BRENT WHITEMAN Company: GEN-DOR OIL Phone: (620) 222-7808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 08/24/2006 1:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

8/12/2006 -- Sanded back at 2865' and dump bailed 6 sacks of cement on top.
8/16/2006 -- Shot 4-1/2" casing at 1508', 1334', and 1209'. POOH with 1209' of 4-1/2" casing.
8/24/2006 -- RIH with tubing at 250'. Gen-Dor mixed and pumped 96 sacks of 60/40 posmix with 4% gel to surface.
United Cement #7296

Perfs:

Top	Bot	Thru	Comments
2980	2984		MISSISSIPPI

RECEIVED
KCC DISTRICT #2
SEP 14 2006

WICHITA, KS
INVOICED

9/20/06
2007060557

RECEIVED
SEP 19 2006

KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT