

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: FIML Natural Resources, LLC
Address: 410 17th St. Suite 900 Denver, CO 80202
Phone: (303) 899-5608 Operator License #: 33476
Type of Well: Oil D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/31/06 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
NA Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-171-20632-00-00
Lease Name: Pratt
Well Number: 16-19-1831
Spot Location (QQQQ): _____ - _____ - SE - SE
635 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 19 Twp. 18 S. R. 31 East West
County: Scott
Date Well Completed: 7/31/06
Plugging Commenced: 7/31/06
Plugging Completed: 7/31/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	324'	8 5/8"	9 jts	0 jts
RECEIVED SEP 22 2006 KCC WICHITA						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set plug #1 2311'-2180' w/ 50 sx cmt to cover anhydrites. Set 2nd plug 1590'-1400' w/ 80 sx cmt below btm depth usable wtr.
Set 3rd plug 811'-680' w/ 50 sx cmt. Set 4th plug 435'-300' w/ 50 sx cmt, 50' above & 50' below base surf csg shoe. Set 5th plug 62' - surf w/ 20 sx cmt. Cmt rat & mouse hole w/ 25 sx. Cmt w/ total of 275 sx 60/40 Cl A/Poz w/ 6% gel & 1/4 pps flocele. Wt: 13.2 ppg
Yield: 1.59 ft3/sk. As per instructions f/ Ken Jehlik w/ KCC. Fluid between cmt plugs is 9.2 ppg; 39 vis fresh wtr mud.

Name of Plugging Contractor: Excell Services, Inc. License #: 8273
Address: 36629 US Highway 385, Wray, CO 80758

Name of Party Responsible for Plugging Fees: FIML Natural Resources, LLC
State of Colorado County, Denver, ss.

Phyllis Sobotik (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Phyllis Sobotik
(Address) 410 17th St. Suite 900 Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 19th day of September, 20 06
Elaine Glinick My Commission Expires: 5/5/2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT