

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
SEP 27 2006
KCC WICHITA

Form CP-4
September 2003
Use or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: K & S Oil

Address: 1520 N. Grimes McPherson, Ks. 67460

Phone: (620) 241-4901 Operator License #: 32381

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-113-21,171-00-00

Lease Name: George White

Well Number: 1

Spot Location (QQQQ): SE SW SW KCC
3070 Feet from _____ North / South Section Line
9/29/06
PKT

4382 Feet from East / _____ West Section Line
Per 1's
Pigs
C PSC

Sec. 24 Twp. 18 S. R. 1 East West

County: McPherson

Date Well Completed: _____

Plugging Commenced: 8-22-06

Plugging Completed: 8-24-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	218'	None
				5-1/2"	2889'	1290'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 2300' and 5 sacks cement. Cut casing loose @1290' and layed down. Bailed fluid down to 300' and set rock bridge and ran 6-1/2 yards slurry mix from 300' to surface. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: K & S Oil

State of Kansas County, Rice, ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 26th day of September, 20 06

Irene Herzberg Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT